



Desktop survey undertaken from google street view with imagery dated: July 2024

All traffic management shall comply with all current legislation and guidance including Chapter 8, Safety at Street Works and Road Works (A Code of Practice).

Pedestrian management to be installed and managed to suit site conditions in accordance with current legislation & codes of practice by the contractor unless otherwise stated.

All signage and road markings shall conform with the Traffic Signs Regulations and General Directions (TSRGD).

Sign locations are indicative only, exact location to be determined on site.

Suitably qualified operative to assess site to ensure the installation complies with all current legislation. Any issues and/or changes from the original design should be immediately reported to the relevant contracts manager/designer.

This design is only valid for 12months from date of production and should be re-evaluated if installation is to take place after this period.

SIGN SCHEDULE	
Qty: 4 Ref: 13.9 Schedule 13-9: Temporary Information	
Qty: 2 Ref: 13.9 Schedule 13-9: Temporary Information	
Qty: 1 Ref: 13.9 Schedule 13-9: Temporary Information	
Qty: 1 Ref: 13.9 Schedule 13-9: Temporary Information	
Qty: 1 Ref: 13.9 Schedule 13-9: Temporary Information	
Qty: 1 Ref: 13.9 Schedule 13-9: Temporary Information	
Qty: 1 Ref: 13.9 Schedule 13-9: Temporary Information	
Qty: 3 Ref: 2702 Schedule 13-9: Temporary diversion route	
Qty: 4 Ref: 2702 Schedule 13-9: Temporary diversion route	
Qty: 2 Ref: 2702 Schedule 13-9: Temporary diversion route	
Qty: 2 Ref: 2703 Schedule 13-9: Temporary diversion route	
Qty: 2 Ref: 2703 Schedule 13-9: Temporary diversion route	
Qty: 2 Ref: 2703 Schedule 13-9: Temporary diversion route	
Qty: 2 Ref: 2704 Schedule 13-9: Temporary diversion route	
Qty: 3 Ref: 2704 Schedule 13-9: Temporary diversion route	
Qty: 1 Ref: 573 Schedule 13-9: Temporary diversion route	
Qty: 1 Ref: 573 Schedule 13-9: Temporary diversion route	
Qty: 6 Ref: 670 Schedule 13-9: Temporary diversion route	
Qty: 8 Ref: 701 Schedule 13-9: Temporary diversion route	
Qty: 10 Ref: 7010-FP-13-9 Schedule 13-9: Temporary hazard ahead - Road Ahead Closed	
Qty: 4 Ref: 7010-FP-13-9 Schedule 13-9: Temporary hazard ahead - Road Closed	

- AWS signage installed at least 2 weeks prior to works commencing. Dates & durations to be confirmed.
- Parked vehicles/parking bays are present and could interfere with the works. No parking cones are to be installed prior to works commencing with appropriate signage if required.
- Bus stop(s) are present/in close proximity to the works. Bus stop(s) are to be suspended and the appropriate signage installed in suitable locations to be agreed on site.
- Denotes location of traffic management operative

Key:	
	Works Area
	Closure
	Vehicular Diversion Route
	Ped Diversion Route
	Cone
	Datum Point
	Temporary Traffic Signal
	Stop & Go Board
	Temporary Ped Signal
	Existing Bus Stop
	Temporary Sign
	Pedestrian Barrier

Safety information:	
Min width of sideways safety zone (S)	0.5m
Min length of longways clearance (L)	0.5m
High Street	

Site information:	
NSG	High Street, Knowle, Solihull
Local Authority	Solihull
USRN	35002225
Road Type	Single lane carriageway
Works Location	X:418154 Y:276753
Surveyed	<input checked="" type="checkbox"/> Bus Stop(s) <input checked="" type="checkbox"/> Parked Vehicles <input checked="" type="checkbox"/>
Perm Signals	<input checked="" type="checkbox"/> Controlled Crossing <input checked="" type="checkbox"/> Cycle Lanes <input checked="" type="checkbox"/>

Chapter 8 details:

Detail B

Notes:
 1) During darkness, warning lights to BS EN 12352:2006 should be provided in accordance with Table A1.3 (Appendix 1).
 2) 45° tapers have 1.2m spacing, no relaxations.
 3) On motorways and NSL AP duals with hard shoulders, 1m cones will be required for both standard and relaxation works for lead tapers and the facing wall of lane changes.

Detail C1

Notes:
 1) During darkness, warning lights to BS EN 12352:2006 should be provided in accordance with Table A1.3 (Appendix 1).
 2) For relaxation to Detail C1 see Table A1.3 (Appendix 1).

Detail C2

Notes:
 1) During darkness, warning lights to BS EN 12352:2006 should be provided in accordance with Table A1.3.

Rev	Date	Comments	By	City
B	28/05/2026	Revised to suit comments	CM	MT
A	14/05/2026	Additional signage added	CM	MT

Balfour Beatty
 Living Places
 Working in Partnership with
traffix

total traffic & event management solutions
 Old Arden Brickworks | Bickenhill | Solihull | West Midlands | B92 0DY
 t +44 (0)800 819 9001 | f +44 (0)1675 442507
 info@traffixuk.com | www.traffixuk.com

Project title:		
Traffic Management		
Drawing title:		
Proposed Road Closure High Street Knowle B93 0NA		
Date: 07/05/226	Scale: NTS	Paper: A2
Drawn: CM	Checked: BN	Approved: MT
Project Number: TFX MT3445	Drawing Number: 001	Revision: B

This drawing is copyright & the property of Traffix & must not be copied in whole or in part without their written permission. Copyright is reserved. ©
 This drawing must not be scaled.
 The Contractor is to report all discrepancies & errors to the Contract Manager prior to works commencing.